

NORTHLINE MECHANICAL

Bid Schedule - Oakfield Medical Office, Tenant Improvement

Bid No. 2026-131

ITEM	DESCRIPTION	QTY	UNIT
M-1	5-ton condensing unit, furnish and install	2	EA
M-2	5-ton air handler, furnish and install	2	EA
M-3	Refrigerant line set, 3/8 x 7/8, 50 ft, insulated	2	EA
	<i>Equipment items total</i>	6	
M-4	Duct wrap insulation, R-6 foil-faced	900	LF
M-5	Galvanized sheet metal ductwork, fabricated and installed	1,800	LB
M-6	Controls wiring allowance	1	LS
M-7	Supply register, 10 x 6	24	EA